

Plantware

Lye Mixing and Storage Facility

Project Details

Project	Ludanlæg - Vejle Havn
Client	Vejle Havn (Vejle Harbour)
Built	PROMECON A/S
Year	2005

PROMECON performed both production of piping and steel work as well as conducting the erection of steel and pipe work.

PlantWare A/S has designed the installations for retrofitting the tank installations for lye production in Vejle Port for PROMECON.

PlantWare made the design based on 3D Plant Design tools from AVEVA Ltd: PDMS.

PlantWare designed

- » Piping installation for lud
- » Piping installation for tank heating
- » Pipe supports
- » Catwalks
- » Access stairs and ladders for storage tanks
- » Steel structure for building

PlantWare delivered

- » GA - general arrangement drawing
- » DA - detail arrangement drawings of different systems, steel structures etc.
- » Piping isometrics
- » Isometric pipe drawings
- » Steel detail drawings for pipe supports
- » Steel detail drawings for steel structure
- » PED - engineering and declaration
- » CE - risk analysis etc.
- » MTO lists for piping components
- » MTO lists for steel elements

PROMECON performed both production of piping and steel work as well as conducted the erection of steel and pipe work.



Work included designs for both the buildings for pump installation and control room. A ramp for servicing the trucks during loading and unloading was added to the building.

Contact



Christian Pallesen
Mobile +45 2526 8805
Mail cp@p-engineering.dk

Plantware

Lye Mixing and Storage Facility

